



Government of India  
Ministry of Environment, Forest and Climate Change  
(Issued by the State Environment Impact Assessment  
Authority(SEIAA), MAHARASHTRA)

To,

The -1

GARVE PATIL CONSTRUCTION COMPANY

S No 51(P), 52(P), Kate Puram Circle, Pimple Gurav, Tal-Haveli, Pune. -  
411061

**Subject:** Grant of Environmental Clearance (EC) to the proposed Project Activity  
under the provision of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application for Environmental Clearance (EC)  
in respect of project submitted to the SEIAA vide proposal number  
SIA/MH/INFRA2/414732/2023 dated 16 Jan 2023. The particulars of the  
environmental clearance granted to the project are as below.

1. EC Identification No.	EC23B038MH153782
2. File No.	SIA/MH/INFRA2/414732/2023
3. Project Type	New
4. Category	B
5. Project/Activity including Schedule No.	8(a) Building and Construction projects
6. Name of Project	Garve Samrajya by M/s Garve Patil Construction Company
7. Name of Company/Organization	GARVE PATIL CONSTRUCTION COMPANY
8. Location of Project	MAHARASHTRA
9. TOR Date	N/A

The project details along with terms and conditions are appended herewith from page  
no 2 onwards.

Date: 08/08/2023

(e-signed)  
Pravin C. Darade , I.A.S.  
Member Secretary  
SEIAA - (MAHARASHTRA)

*Note: A valid environmental clearance shall be one that has EC identification  
number & E-Sign generated from PARIVESH. Please quote identification  
number in all future correspondence.*

*This is a computer generated cover page.*

PARIVESH

(Pro-Active and Responsive Facilitation by Interactive,  
and Virtuous Environmental Single-Window Hub)



## STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

No. SIA/MH/INFRA2/414732/2023  
Environment & Climate  
Change Department  
Room No. 217, 2<sup>nd</sup> Floor,  
Mantralaya, Mumbai- 400032.

To  
M/s Garve Patil Construction Company,  
S No 51(P), 52(P), Pimple Gurav,  
Tal- Haveli, Pune.

Subject : Environmental Clearance for proposed construction project "Samrajya"  
at S No 51(P), 52(P), Pimple Gurav, Tal- Haveli, Pune by M/s Garve  
Patil Construction Company

Reference : Application no. SIA/MH/INFRA2/414732/2023

This has reference to your communication on the above-mentioned subject. The proposal was considered by the SEAC-3 in its 166<sup>th</sup> meeting under screening category 8 (a) B2 as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 261<sup>st</sup> (Day-1) meeting of State Level Environment Impact Assessment Authority (SEIAA) held on 09.06.2023.

2. Brief Information of the project submitted by you is as below:-

1.	Proposal Number	SIA/MH/INFRA2/414732/2023	
2.	Name of Project	"Samrajya" by M/s Garve Patil Construction Company	
3.	Project category	8(a)	
4.	Type of Institution	Private	
5.	Project Proponent	Name	Mr. Vinayak Garve
		Regd. Office address	Samrajya Society Survey No 51 ( P) 52 (P) Kate Puram Circle Pimple Gurve Pune 411061.
		Contact number	9545552300
		e-mail	sachin.garvedevelopments@gmail.com
6.	Consultant	Sneha Hi-tech Products, Bangalore NABET/EIA/2124/RA023	
7.	Applied for	New	
8.	Details of previous EC	NA	
9.	Location of the project	S No 51(P), 52(P), Pimple Gurav, Tal- Haveli, Pune.	
10.	Latitude and Longitude	Latitude – 18°35'05.23"N Longitude 73°48'55.69"E	
11.	Total Plot Area (m <sup>2</sup> )	21787.42 m <sup>2</sup>	
12.	Deductions (m <sup>2</sup> )	3255.02 m <sup>2</sup>	
13.	Net Plot area (m <sup>2</sup> )	18532.40 m <sup>2</sup>	
14.	Proposed FSI area (m <sup>2</sup> )	73016.29 m <sup>2</sup>	
15.	Proposed non-FSI area (m <sup>2</sup> )	38345.65 m <sup>2</sup>	

16.	Proposed TBUA (m <sup>2</sup> )	111361.94 m <sup>2</sup>				
17.	TBUA (m <sup>2</sup> ) approved by Planning Authority till date	111361.94 m <sup>2</sup> (FSI- 73016.29 m <sup>2</sup> + Non FSI- 38345.65 m <sup>2</sup> )				
18.	Ground coverage (m <sup>2</sup> ) & %	5092.31 m <sup>2</sup> 23.37 % of Total Plot area (21787.42 m <sup>2</sup> ) 27.47 % of Net Plot area (18532.40m <sup>2</sup> )				
19.	Total Project Cost (Rs.)	Rs 240 Cr.				
20.	CER as per MoEF & CC circular dated 01/05/2018	-				
<b>Details of Building Configuration:</b>						
<b>Previous EC / Existing Building</b>			<b>Proposed Configuration</b>			<b>Reason for Modification / Change</b>
<b>Building Name</b>	<b>Configuration</b>	<b>Height (m)</b>	<b>Building Name</b>	<b>Configuration</b>	<b>Height (m)</b>	
-	-	-	WING A	2B+G+6 Fl	23.75	Plot Amalgamation & UDCPR 2020
-	-	-	WING B	2B+GP+21Fl	69.05	
-	-	-	WING C	2B+GP+21 Fl	69.05	
WING D	P+7 Fl	29.95	WING D	P+9 Fl	29.95	
WING E & F	P+7 Fl	23.95	WING E & F	P+7 Fl	23.95	
-	-	-	WING G	2B+GP+21Fl	69.05	
-	-	-	WING H	2B+GP+21Fl	69.05	
22.	Tenements- 97 Nos.	Tenements- 655 Nos. Shops- 25 Nos, Offices- 55 Nos.				
23.	Water Budget	<b>Dry Season (m<sup>3</sup>/day)</b>		<b>Wet Season (m<sup>3</sup>/day)</b>		
		Fresh Water	332 m <sup>3</sup> /day	Fresh Water	332 m <sup>3</sup> /day	
		Recycled water for Gardening	25.00 m <sup>3</sup> /day	Recycled water for Gardening	0.00 m <sup>3</sup> /day	
		Swimming Pool	NA	Swimming Pool	NA	
		Recycled water for Flushing	177 m <sup>3</sup> /day	Recycled water for Flushing	177 m <sup>3</sup> /day	
		Total	534 m <sup>3</sup> /day (One Time)	Total	509 m <sup>3</sup> /day (One Time)	
	Treated excess water generation	256 m <sup>3</sup> /day	Treated excess water generation	281 m <sup>3</sup> /day		
24.	Water Storage Capacity for	Domestic UG tank Capacity: 401 m <sup>3</sup> Flushing water tank Capacity: 177 m <sup>3</sup>				

	Firefighting/UGT	Fire UG tank Capacity: 400 m <sup>3</sup>		
25.	Source of water	Pimpri-Chinchwad Municipal Corporation		
26.	Rainwater Harvesting (RWH)	Level of the Ground water table:	Pre-Monsoon:.8m to 12 m BGL Post Monsoon: 2 m to 5 m BGL	
		Size and no of RWH tank(s) and Quantity:	Not Applicable	
		Quantity and size of recharge pits:	12 Nos. (5 No for surface water harvesting & 7 No for roof top rain water harvesting) A recharge structure of Length 2 Mt., Width 2 Mt. and Height 2 Mt. with 60 M deep recharge bore well with 1 number of 2 M length, 2 M Width and 3 M deep de-silting chamber with O & G Trap.	
		Details of UGT tanks if any:	NA	
27.	Sewage and Wastewater	Sewage generation in CMD:	458 m <sup>3</sup> /day	
		STP technology:	MBBR	
		Capacity of STP (CMD):	400 m <sup>3</sup> /day & 70 m <sup>3</sup> /day	
28.	Solid Waste Management during Construction Phase	<b>Type</b>	<b>Quantity (kg/d)</b>	<b>Treatment / disposal</b>
		Dry waste:	10.00 Kg/Day	Send to Authorized Vendor
		Wet waste:	15.00 Kg/Day	Send to Authorized Vendor
		Construction waste	25.00 Kg/Day	Will be used for Leveling
29.	Solid Waste Management during Operation Phase	<b>Type</b>	<b>Quantity (kg/day)</b>	<b>Treatment / disposal</b>
		Dry waste:	879 Kg/day	Handed over to Authorized Vendor
		Wet waste:	1132 Kg/day	Organic Waste Converter
		Hazardous waste:	NA	NA
		Biomedical waste	NA	NA
		E-Waste	3128 Kg/year	Handed over to Authorized Vendor
30.	Green Belt Development	Total RG area (m <sup>2</sup> ):	1858 m <sup>2</sup>	
		Existing trees on plot:	05 Nos.	
		Number of trees to be planted:	243 Nos.	
		Number of trees to be cut:	NA	
		Number of trees to be transplanted:	NA	
31.	Power requirement:	Source of power supply:	MSEDCL	
		During Construction Phase (Demand Load):	45 KW	
		During Operation phase (Connected load):	4655 KW	

		During Operation phase (Demand load):	2389 KW		
		Transformer:	630 KVA - 4 Nos., 315 KVA- 1 No		
		DG set:	320 KVA -1No for residential, 62.5 KVA- 1 No for commercial		
		Fuel used:	HSD		
32.	Details of Energy saving	<ul style="list-style-type: none"> <li>➤ Generally we have proposed high efficiency transformer, motors etc. to reduce losses.</li> <li>➤ Electronic Ballasts and Energy efficient lamp source either triposphere or LED are proposed for common area &amp; general lighting with automatic time based control to save power by switching ON &amp; OFF the lights at appropriate time. The estimated saving in common lighting consumption is up to 24 % due to adopting above measures.</li> </ul>			
33.	Environmental Management plan budget during Construction phase	<b>Type</b>	<b>Details</b>	<b>Cost</b>	
		Capital Cost	Site Barricading, Personal Protective Equipment, Site Sanitation- Mobile toilets& Debris Management	88.00 Lakh	
		O & M Cost	Water for Dust Suppression, Air & Noise Monitoring, Tanker Water for Construction & Labour, Water Monitoring, Disinfection- Pest Control, First Aid Facilities, Health Check Up, Creches for Children, Food for children.	62.00 Lakh/Year	
34.	Environmental Management plan Budget during Operation phase	<b>Component</b>	<b>Details</b>	<b>Capital (Rs.) Lakh</b>	<b>O&amp;M (Rs. Lakh /Year )</b>
		Storm Water	Storm Water Piping	NA	NA
		Sewage treatment	Capacity 400 KLD	60.00	17.00
		Sewage treatment	Capacity 70 KLD	10.78	8.18
		Water treatment	NA	NA	NA
		RWH	Rain Water Harvesting	18.00	2.50
		Swimming Pool	NA	NA	NA
		Solid Waste	Organic Waste Convertor	19.00	8.94
			Dry waste Management	-	----
		Hazardous waste	NA	NA	NA
		E-waste	-	-	0.50
Biomedical waste management	-	-	1.00		

		Green belt development	-	59.42	10.70
		Energy System	-	1.20 Cr	2.50
		Environmental Monitoring	-	-	2.50
		Disaster Management	-	970	41.60
35.	Traffic Management	<b>Type</b>	<b>Required as per DCR</b>	<b>Actual Provided</b>	<b>Area per parking (m<sup>2</sup>)</b>
		4-Wheeler	745	753	Open Parking= 25m <sup>2</sup> Covered Parking= 30m <sup>2</sup> Basement Parking= 35 m <sup>2</sup>
		2-Wheeler	2221	2221	3.00 m <sup>2</sup>
36.	Details of Court cases / litigations w.r.t. the project and project location, if any.				NA

3. The proposal has been considered by SEIAA in its 261<sup>st</sup> (Day-1) meeting held on 09.06.2023 and decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

**Specific Conditions:**

**A. SEAC Conditions-**

1. PP to abide all the conditions of fire NoC.
2. PP to provide electric charging facility by providing charging points at suitable places as per Maharashtra Electric Vehicle Policy,2021.
3. PP to ensure that, the water proposed to be used for construction phase should not be drinking water. They can use recycled water or tanker water for proposed construction.

**B. SEIAA Conditions-**

1. PP has provided mandatory RG of 1853.24 m2 on mother earth. Local planning authority to ensure the compliance of the same.
2. PP to keep open space unpaved so as to ensure permeability of water. However, whenever paving is deemed necessary, PP to provide grass pavers of suitable types & strength to increase the water permeable area as well as to allow effective fire tender movement.
3. PP to achieve at least 5% of total energy requirement from solar/other renewable sources.
4. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA.III dt.04.01.2019.
5. SEIAA after deliberation decided to grant EC for – FSI-7301629 m2, Non FSI-38345.65 m2, Total BUA- 111361.94 m2. (Plan approval No-BP/EC/Pimple Gurav/01/2023, dated-17.02.2023)

**General Conditions:**

**a) Construction Phase :-**

- I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.
- III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- IV. Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
- V. Arrangement shall be made that waste water and storm water do not get mixed.
- VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.
- VII. The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- VIII. Permission to draw ground water for construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
- IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- X. The Energy Conservation Building code shall be strictly adhered to.
- XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- XII. Additional soil for levelling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
- XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
- XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- XVI. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle shall be adequately covered to avoid spillage/leakages.
- XVII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
- XVIII. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and

conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.

- XIX. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.

**B) Operation phase:-**

- I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
- III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/ reused to the maximum extent possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give 100 % treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.
- IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.
- V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
- VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- VII. PP to provide adequate electric charging points for electric vehicles (EVs).
- VIII. Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
- IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
- X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.
- XI. The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at



Website at parivesh.nic.in

- XII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
- XIII. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO<sub>2</sub>, NO<sub>x</sub> (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.

**C) General EC Conditions:-**

- I. PP has to strictly abide by the conditions stipulated by SEAC & SEIAA.
- II. If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
- IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
- V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
- VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.
- VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.

4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.

5. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before

starting proposed work at site.

6. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.

7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, amended from time to time.

8. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.

9. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1<sup>st</sup> Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.



Pravin Darade  
(Member Secretary, SEIAA)

Copy to:

1. Chairman, SEIAA, Mumbai.
2. Secretary, MoEF & CC, IA- Division MOEF & CC
3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
4. Regional Office MoEF & CC, Nagpur
5. District Collector, Pune.
6. Commissioner, Pimpri Chinchwad Municipal Corporation
7. Regional Officer, Maharashtra Pollution Control Board, Pune.

